



**KERALA STATE CO-OPERATIVE BANK LTD,  
HEAD OFFICE, CO-BANK TOWERS, PALAYAM  
THIRUVANANTHAPURAM**

P&E/PJP Br/1625/2058/2018-19

19.09.2018

**Quotation Notice**

Quotation for providing Two wheelers parking shed at  
Poojappura Branch of Kerala State Co-operative Bank Ltd-reg.  
-----

Competitive quotations in sealed covers super scribing the name of works are invited from the Registered contractors in appropriate class of Registration of State PWD/CPWD/Authorised experience Agencies/firms/persons for the following work so as to reach the office of the under signed not later than **4.00 PM on or before 29.09.2018**.

Sl. No	Name of work	Time of completion
1	Providing Two wheelers parking shed at Poojappura Branch of Kerala State Co-operative Bank Ltd.,	10 days

The quotation schedule will be issued during office hour on all working days/7 days prior to and up to 1.00 PM on the last date of receipt of quotation. The document can also down loaded from the Bank website ([www.keralacobank.com](http://www.keralacobank.com) )

The quotation will be opened in the presence of contraction or their authorised agents at 4.30PM on the same day. The selected contractors will have to execute an agreement on stamp paper worth Rs.100/- in the prescribed form furnishing with a security deposit receipt covering 5% thê quoted amount drawn in favour of the Managing Director, KSCB Ltd., Thiruvananthapuram. The undersigners reserve the right to reject any or all the quotation with out assigning any reasons.

Sd/-  
Managing Director

**SCHEDULE OF ITEMS**

Name of Project : **Providing Two Wheelers parking shed @  
Poojappura Branch of Kerala State  
Co-operative Bank Ltd.,**

-----

**Period of Completion : 10 days**

<b>Sl. No.</b>	<b>Particulars</b>	<b>Quantity</b>	<b>Rate</b>	<b>Total (Incl. GST)</b>
1	Providing and fixing minimum 0.35 mm or nearest available thickness, power coated Trafford sheet with overlaps of 150mm at ends , on a GI Rectangular Tube common rafter of Size 3 x 1 1/2" with GI Rectangular tube Purlin of size 1 1/2 x 1". The entire structure should be supported by 3" dia GI post at a interval of 2.5 Mtr of total span. Vertical post should be fixed in ground with suitable nuts/bolts or cement concrete. The sheet shall be fixed using self drilling/self tapping screws of size (5.5 x 55 mm) with EPDM seal & the structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including, cutting, hoisting, fixing in position and applying a primary coat of approved steel primer, including all cost, materials, conveyance, Labour charge etc, complete	27 M <sup>2</sup>		

2	Providing and fixing 100 mm dia PVC half cut section with bracket at the end of sheet or tiled roof rain water collection including all cost, materials, conveyance, Labour charge etc, complete.	10 Mtr.		
---	---	---------	--	--

**Special Terms and Conditions**

- 1) Any overhead charges such as unloading of materials etc. should be bear by the Contractor.
- 2) Statutory deductions such as GST etc. will be deducted from the bill amount.
- 3) The Scaffolding and working platforms are to be provided without obstructing the main entrance door so as to enable the entry and exit of persons to the building.
- 4) The time of completion of the work is maximum 10 days from the date of releasing work order and that the Contractor should complete the work within that period. Undue and avoidable delay in the execution of the work will render the Contractor liable to penalty, Rs.100/- per day.
- 5) The rate mentioned in the schedule is firm and the payment will be made by measuring the area after completion of the work in all respect against the measured quantity of work. Full payment will be made only after satisfactory completion of the work.
- 6) The work\* should be guaranteed for one year from the date of completion against any damages/leakage noticed during the period. Further the Contractor should assure company warranty for the Sheets for a period not less than 5 years (Bill copy of the material should be produced). Sheets should be of approved make and good quality with ISI Certification.
- 7) Agreement should be executed for the work in the standard format within 5 days on receipt of this letter of acceptance of quotation.

WIB CO..3..  
WIB CO-BA..  
-LEUVANA..

- 8) Any disputes which may arise between the contractor and the Bank under this agreement shall be referred to Arbitration as per the arbitration clause as contemplated under the Kerala Co-operative Societies Act 1969. Also the decision and award of the Arbitrator shall be final and binding on the contractor and the Bank.

Sd/-  
Managing Director